













SELSports - Case Study England Hockey, The Stoop



KEY FIGURES 6,200m² Pitch Area 24,800no. Permavoid Units 2 days to install

KEY CONTACTS

Client: England Hockey Partnership: STRI, FIH, Polytan, Polypipe, Harlequins, Sport England

Date: June 2019

THE SCHEME

As part of an initiative to raise the profile of hockey, England Hockey and its partners, including UK Sport and the National Lottery, have been investing in new innovative pitch technologies which will make it possible to host temporary hockey events at the highest level in the most prestigious stadiums throughout the UK.

The first stadium to be transformed to host the FIH Pro League double header finals against New Zealand's Black Sticks is The Stoop, home of the Harlequins. This pioneering event will see the largest hockey attendance in the UK since the 2012 Olympics.

THE SOLUTION

The innovative pitch technologies had to deliver a top class hockey surface and the ability for install / removal in a short time window without damaging the rugby pitch beneath for the Harlequins' upcoming season.

SELSports were selected to execute the installation and removal of the Permavoid drainage system to exacting standards and within a rigid time frame.

Scrupulous attention to detail made it possible to install 6200m2 of Permavoid units to an impeccable tolerance of just +/-2mm. Superior material, plant and labour coordination made it possible to complete the perfect Permavoid installation in just two days. SELSports are proud to have completed this installation before the scheduled installation start date.

www.selsports.co.uk